



NAVSARI AGRICULTURAL UNIVERSITY
OFFICE OF THE EXECUTIVE ENGINEER
NAVSARI- 396 450

No. NAU/EE/B.2/ 6203-04 /2020

Date: 15-10-2020

To,

1. All interested Bidder for Below Mentioned Work. (By Web Publication through www.nau.in)
2. The Notice Board of All offices of NAU. (By Web Publication through www.nau.in)

Name of Work:- Repairing and Renovation E-Type Quarter (E-2) at NAU Navsari.
 Gentleman,

Sealed & Super scribed quotations on A-1/A-2 Tender Basis are invited as per Schedule-B, So as to reach this office on or before 22-10-2020 By Post/courier only before 18:00 hours. The work shall be carried out immediately and complete the same as early as possible after the issue of work order.


Schedule – B

Name of work:- Repairing and Renovation E-Type Quarter (E-2) at NAU Navsari.

ABSTRACT SHEET

It No.	Description	Qty	Rate	Labour cess 1%	Rate with L.C.	Per	Amount
1	Dimolition and Disposal of unserviceable material with all lead & Lift (i) Grill -L/S	9.00	150.00	1.50	151.50	Nos	1363.50
2	Dismentaling Doors, Windows, Ventilators etc. (Wood or steel) shutters including chowkhats architraves holdfasts and other attachment etc. complete and stacking them within all lead and lift (i) Not exceeding 3Sq.M. in area. (S.O.R./20013A/20.49/Pg-164)	4.00	118.00	1.18	119.18	Nos	476.72
3	Providing and fixing M.S. GRILL of required pattern at balcony, in window frames, in RCC, in Masonry etc. with M.S. flats at required spacing and frame all around, square or round bars with round headed bolts by nuts / screws at all heights including welding, grinding, fixing in position, applying ready mixed red lead priming coat and painting two coats of enamel paint of asian/berger make etc., complete as per detailed drawing and directed by E.I.C.(RA)	351.00	70.24	0.70	70.94	Kg	24900.78
4	Providing and laying 18mm thick polished GRANITE STONE SLAB in riser of steps, dedo & skirting laid on 10mm thick cement mortar 1:3 (1 Cement : 3 Coarse sand) and jointed with coloured slurry including rubbing & polishing etc complete in true line and level / slope as directed by E.I.C. -R.A.	4.20	2044.24	20.44	2064.68	Smt	8671.67
5	Providing and fixing standard extruded of alluminium section of size 63mm x 38.10mm x 1.2mm (jindal section:2434, @ Wt. 0.643 Kg/mt) with colour anodized alluminium frame for ventilation with 5mm thick frosted glass as details etc complete for ventilation (S.O.R./11030/0/Pg-119)	2.70	1386.00	13.86	1399.86	Smt	3779.62

6	Repairing of existing Door, window, etc including providing S.S fixtures, hinges etc as requirement and make it workable condition etc, complete as directed by EIC	16.00	1358.36	13.58	1371.94	Nos	21951.10
7	Providing and fixing screw down Bib taps (EDLIN - JET Collection) of following size.(Gun metal screw down Bib Tap. 15mm (RA)	10.00	699.30	6.99	706.29	Nos	7062.93
8	Providing and fixing pillar tap (EDLIN - JET Collection) , capstan head, screw down high pressure with screw, shanks and back nuts. (RA)	2.00	810.35	8.10	818.45	Nos	1636.91
9	Providing and fixing Flush Cock (EDLIN - JET Collection) with Adjustable wall flange (25mm) With Exposed Shut off provision & Round Flange of approved quality including fixing in pipe line etc. complete. 40 mm dia. (RA)	1.00	1770.45	17.70	1788.15	Nos	1788.15
10	Providing and fixing brass screw down CON. Stop Cock With Adjustable Wall Flange (EDLIN - JET Collection) . 15mm dia.(RA)	2.00	1121.10	11.21	1132.31	Nos	2264.62
	Total Rs.						73896.00


Executive Engineer

Navsari Agricultural University
Navsari

I/We agree to Carry out and complete the work at.....% (In Figure)
..... Percentage (In Words) Above / Below than the
estimated cost as mentioned above.

Terms and Conditions: -

1. In general the work shall be carried out as per the instruction of Engineer in-charge and as per the details specification of item.
2. The rate shall include all cost of materials, scaffolding, Tool plants and labours involved in satisfactory completion of work as per specification as above.
3. All the work shall be carried out such a way that it may not cause any Damage to existing work/building.
4. All the materials shall be got approved before use.
5. Rate Quatated should be inclusive of all taxes.

Date:

stamp and Signature of Contractor:

Executive Engineer
Navsari Agricultural University
Navsari